



Department of Public Services
5228 South Isabella Road
Mt. Pleasant, MI 48858
Phone (989) 772 4600 ext. 224
E Mail ksmith@uniontownshipmi.com

Date: March 24, 2025

ADDENDUM NUMBER 1

PROJECT

Charter Township of Union

Isabella Road Well Site – 2025 - Well #10 Well Maintenance

BIDS DUE

Date: April 16, 2025
Time: 10:00 AM
Location:
Charter Township of Union
5228 South Isabella Road
Mt. Pleasant, MI 48858

The Addendum is issued prior to the receipt of bid proposals to amend the Contract Documents as follows. **Bidders shall acknowledge receipt of this addendum by means of a handwritten note on the Bid Schedule.**

Project Specifications can be found as follows:

[http://www.uniontownshipmi.com/Departments/PublicServicesDepartment/RequestforProposals\(RFP\)-PublicServicesDepartment.aspx](http://www.uniontownshipmi.com/Departments/PublicServicesDepartment/RequestforProposals(RFP)-PublicServicesDepartment.aspx)

Requirements:

Contractor shall be responsible for including, but are not limited to, all the labor, materials, and equipment necessary for completing the cleaning, televising, and rehab of well #10. The following items should be included in each detailed proposal:

- Mobilization/Demobilization
- Pull Pumps
- Replace Drop Pipes (6" - Certa Lok Drop Pipe shall be provided if needed)
- Start-up
- Chlorinate and sample wells
- Clean and Treat wells
- Post - Video Well Inspections
- Site Restoration and/or Cleanup

Addition to this section:

- **Replace Franklin Electric Pump, 15 HP Franklin Electric Motor, wire for 15hp motor, and stainless-steel check valve.**

- **Pump:** The pump shall be constructed with stainless steel impellers and diffusers, a stainless-steel shell to maintain alignment, and a heavy investment cast stainless steel. Stainless steel suction and discharge brackets.
- **Motor:** The motor shall be supplied to match the above pump configuration and manufacturer (Franklin), constructed of stainless steel.
- **Pump & motor shall be provided with a five (5) year warranty for all parts & labor.**
- **Check Valve:** A stainless-steel check valve shall be placed in line of the pump and drop pipe.

This Addendum No. 1 becomes part of the Contract Documents as of this date and supersedes the information in the originally issued Contract Documents where applicable. **The Contractor shall acknowledge receipt of the Addendum in the Bid Schedule included with his/her bid.**

Addendum No 1